



Procurement of Construction Materials for WFP Project

Company Name: ()

Delivery Location: Guzara District - Targeted Villages

Annex #3

#	Items Discription	QTY	UoM	Unit Cost AFN	Total Cost AFN	Remark
1	<p>Washed and sifted Sand with size of less than 5mm (Should be hard, durable, clean and free from organic matter) with transportation, it is mentionable that the items will be transported to 3 villages in Guzara district which the distance is 50 KM far away from Herat city.</p> <p>Vendors might assure the quality of all provided items, otherwise if the items are rejected by technical team replacing cost responsibilities are with vendors. Cost of All types of tests requested by the technical engineer might be included in the quotation.</p> <p>ماسه شسته سرنده شده از غربال 5 ملی متر (باید سخت، بادوام، پاک و عاری از مواد خارجی باشد) همراهی هزینه حمل و نقل به تمام پروژه های فرعی در نظر گرفته شود، قابل ذکر است که این قلم به 3 قریه ولسوالی گذره که فاصله آنها 50 کیلومتر از شهر هرات می باشد انتقال داده می شود</p> <p>شرکت ها باید کیفیت تمام اقلام ارایه شده را تضمین کنند در صورت رد شدن اقلام توسط تیم تخنیک هزینه جایگزین به مسولیت شرکت ها است و هزینه تست های که از طرف تیم تخنیک تعین میشود به عهده شرکت می باشد</p>	150	m3			
2	<p>Washed Sand and Gravel with size of less than 20mm (Should be hard, durable, clean and free from organic matter) with transportation, it is mentionable that the items will be transported to 3 villages in Guzara district which the distance is 50 KM far away from Herat city.</p> <p>Vendors might assure the quality of all provided items, otherwise if the items are rejected by technical team replacing cost responsibilities are with vendors. Cost of All types of tests requested by the technical engineer might be included in the quotation.</p> <p>ماسه و جغل شسته سرنده شده از غربال 20 ملی متر (باید سخت، بادوام، پاک و عاری از مواد خارجی باشد) همراهی هزینه حمل و نقل به تمام پروژه های فرعی در نظر گرفته شود، قابل ذکر است که این قلم به 3 قریه ولسوالی گذره که فاصله آنها 50 کیلومتر از شهر هرات می باشد انتقال داده می شود</p> <p>شرکت ها باید کیفیت تمام اقلام ارایه شده را تضمین کنند در صورت رد شدن اقلام توسط تیم تخنیک هزینه جایگزین به مسولیت شرکت ها است و هزینه تست های که از طرف تیم تخنیک تعین میشود به عهده شرکت می باشد</p>	200	m3			
3	<p>High quality Stone (Stright Shaped at least on the both sides, Hard, Well Shaped, and sized, crashed, Free from cavities, cracks, or patches and without soft or loose materials) should be between 15 to 35 cm in size and sourced from the Gazargah or shaidai areas . the stone will be measured and calculated based on cubic meters of work , including transportation costs to all project sites. it is mentionable that the items will be transported to 3 villages in Guzara district which the distance is 50 KM far away from Herat city.</p> <p>Vendors might assure the quality of all provided items, otherwise if the items are rejected by technical team replacing cost responsibilities are with vendors. Cost of All types of tests for Stone requested by the technical engineer might be included in the quotation.</p> <p>سنگ با کیفیت بالا (دم دار یا نما دار حداقل دوطرف نما داشته باشد، سخت، شکل و اندازه مناسب ، شکسته، بدون حفره، ترک یا درز، بدون مواد نرم یا سست) سایز سنگ بین 15 الی 35 سانتی باید باشد واز منابع گازرگاه یا شیدایی تهیه شود همچنان برمنای مازمکعب کارشده محاسبه خواهد گردید. همراهی هزینه حمل و نقل به تمام پروژه ها درنظرگرفته شده ، قابل ذکر است که این قلم به 3 قریه ولسوالی گذره که فاصله آنها از شهر هرات 50 کیلومتر است، انتقال می یابد.شرکت ها باید کیفیت تمام اقلام ارایه شده را تضمین کنند در صورت رد شدن اقلام توسط تیم تخنیک هزینه جایگزین به مسولیت شرکت ها است و هزینه تست های که از طرف تیم تخنیک تعین میشود به عهده شرکت می باشد</p>	200	m3			
4	<p>Cement (High quality Portland Cement type-2, Fresh and not rigid, Bag weight=50 KG, packed well and not teared) With transportation, it is mentionable that the items will be transported to 3 villages in Guzara district which the distance is 50 KM far away from Herat city.</p> <p>Vendors might assure the quality of all provided items, otherwise if the items are rejected by technical team replacing cost responsibilities are with vendors. The cost of all types of tests, if required and requested by the technical engineer, may be included in the quotation.</p> <p>سمنت (سمنت پرتلند نوع 2 با کیفیت بالا، تازه و غیرسخت، وزن کیسه = 50 کیلوگرم، به خوبی بسته بندی شده و پاره نشده) همراهی هزینه حمل و نقل به تمام پروژه های فرعی در نظر گرفته شود، قابل ذکر است که این قلم به 3 قریه ولسوالی گذره که فاصله آنها 50 کیلومتر از شهر هرات می باشد انتقال داده می شود</p> <p>شرکت ها باید کیفیت تمام اقلام ارایه شده را تضمین کنند در صورت رد شدن اقلام توسط تیم تخنیک هزینه جایگزین به مسولیت شرکت ها است و هزینه تست های که از طرف تیم تخنیک درصورت نیاز تعین شد به عهده شرکت می باشد</p>	1000	bag			
5	<p>The mixture (gravel with Sand and soil) should contain 10 to 15 percent soil, achieving a minimum of 95 percent compaction (this mixture is used in the base layer of the road). The size of the gravel should be less than 30 millimeters. With transportation, it is mentionable that the items will be transported to 2 villages in Guzara district which the distance is 50 KM far away from Herat city.</p> <p>Vendors might assure the quality of all provided items, otherwise if the items are rejected by technical team replacing cost responsibilities are with vendors. The cost of all types of tests, if required and requested by the technical engineer, may be included in the quotation.</p> <p>مخلوط (جغل همراهی ریگ و خاک) 10 الی 15 فیصد خاک داشته باشد که حداقل 95 فیصد تراکم را به دست آورد (این مخلوط در لایه اساس سرک استفاده می شود) اندازه جغل کمتر از 30 ملی متر باشد . همراهی هزینه حمل و نقل به تمام پروژه های فرعی در نظر گرفته شود، قابل ذکر است که این قلم به 2 قریه ولسوالی گذره که فاصله آنها 50 کیلومتر از شهر هرات می باشد انتقال داده می شود</p> <p>شرکت ها باید کیفیت تمام اقلام ارایه شده را تضمین کنند در صورت رد شدن اقلام توسط تیم تخنیک هزینه جایگزین به مسولیت شرکت ها است و هزینه تست های که از طرف تیم تخنیک درصورت نیاز تعین شد به عهده شرکت می باشد</p>	1590	m3			

6	<p>Crushed Washed Sand with size of less than 5mm (Should be hard, durable, clean and free from organic matter)with transportation, it is mentionable that the items will be transported to 2 villages in Guzara district which the distance is 50 KM far away from Herat city.</p> <p>Vendors might assure the quality of all provided items, otherwise if the items are rejected by technical team replacing cost responsibilities are with vendors. Cost of All types of tests requested by the technical engineer might be included in the quotation.</p> <p>ماسه شسته کرش ریگریشن با اندازه کمتر از 5 ملی (باید سخت، بادوام، پاک و عاری از مواد خارجی باشد) همراهی هزینه حمل و نقل به تمام پروژه های فرعی در نظر گرفته شود، قابل ذکر است که این قلم به 2 قریه ولسوالی گذره که فاصله آنها 50 کیلومتر از شهر هرات می باشد انتقال داده می شود</p> <p>شرکت ها باید کیفیت تمام اقلام ارائه شده را تضمین کنند در صورت رد شدن اقلام توسط تیم تخنیکي هزینه جایگزین به مسولیت شرکت ها است و هزینه تست های که از طرف تیم تخنیکي تعیین میشود به عهده شرکت می باشد</p>	150	m3			
7	<p>Crushed Washed Fine and Coarse Aggregate with size of less than 20mm (Should be hard, durable, clean and free from organic matter) with transportation, it is mentionable that the items will be transported to 2 villages in Guzara district which the distance is 50 KM far away from Herat city.</p> <p>Vendors might assure the quality of all provided items, otherwise if the items are rejected by technical team replacing cost responsibilities are with vendors. Cost of All types of tests requested by the technical engineer might be included in the quotation.</p> <p>ریگ شسته کرش ریگریشن نخودی و بادی با اندازه کمتر از 20 ملی (باید سخت، بادوام، پاک و عاری از مواد خارجی باشد) همراهی هزینه حمل و نقل به تمام پروژه های فرعی در نظر گرفته شود، قابل ذکر است که این قلم به 2 قریه ولسوالی گذره که فاصله آنها 50 کیلومتر از شهر هرات می باشد انتقال داده می شود</p> <p>شرکت ها باید کیفیت تمام اقلام ارائه شده را تضمین کنند در صورت رد شدن اقلام توسط تیم تخنیکي هزینه جایگزین به مسولیت شرکت ها است و هزینه تست های که از طرف تیم تخنیکي تعیین میشود به عهده شرکت می باشد</p>	150	m3			
Total Cost in AFN						