

RFQ of Plaster work for Yoldoz Primary Mix School at Faryab province

announcement No: DAARTT-243/02022023

Background:

DAARTT (Danish Assistance to Afghan Rehabilitation and Technical Training) is an INGO established in Afghanistan by the Danish People's Aid (DPA) in 2004. DAARTT is specialized in construction and capacity building in all aspects of construction. DAARTT's core staff consists of experienced Afghan engineers, architects, and management board. DAARTT has constructed more than 100 schools, clinics, and other buildings. Recently DAARTT has Started Humanitarian program as well in Afghanistan.

Item description and specification:

#	Description	unit	Quantity	Unit cost	Total cost
1	Internal plasterwork of walls including ceilings (main building, guardroom, latrine) without materials.	M ²	1660		
2	External plasterwork of walls including peak and parapet walls (main building, guardroom, and latrine) without materials.	M ²	700		
3	Boundary wall plaster work including	M ²	756		
Total Amount					

مشخصات امور پلاستر کاری با کیفیت عالی بشکل ایرانی:

پلاستر کاری سقف ها در سه مرحله (1 - در مرحله اول چتکه کاری توسط ریگ درشت و سمنت 2- در مرحله دوم پلاستر کاری توسط ریگ درشت و سمنت 3- در مرحله سوم صاف کاری توسط ریگ میده و سمنت) صورت میگیرد.

پلاستر کاری دیوار ها در دو مرحله (1 - در مرحله اول پلاستر کاری توسط ریگ درشت و سمنت 2- در مرحله دوم صاف کاری توسط ریگ میده و سمنت) صورت میگیرد.

شرایط پلاستر کاری سقف ها، گادر ها، پایه های کانکریتی باید تحت شرایط ذیل در سه مرحله صورت گیرد:

- در مرحله اول قبل شروع کار پلاستر کاری باید سطوح متذکره مرطوب شده با استفاده از سمنت و ریگ درشت چتکه کاری شود و برای مدت لازمه جهت رسیدن به مقاومت سطوح چتکه کاری شده بشکل درست و اساسی آبدهی و مرطوب نگهداشته شود.
- در مرحله دوم بعد از مدت چند یوم کار پلاستر کاری لایه دوم توسط ریگ درشت و سمنت پلاستر کاری گردد.
- در مرحله سوم قبل از اینکه پلاستر کاری (لایه یی درشت) به مقاومت نهایی برسد، باید توسط ریگ میده و سمنت صاف کاری انجام شود. در مرحله سومی باید لایه دومی و سومی همزمان پرکاری و صاف کاری گردد.
- تمام سطوح پلاستر کاری باید شاقولی باشد.
- مصالحه برای چتکه و پلاستر مطابق به لست مشخصات مخلوط گردد.

شرایط پلاستر کاری دیوار های داخلی، خارجی، دیوار احاطه، پاراپت و پیک ها باید تحت شرایط ذیل صورت گیرد:

- در مرحله اول قبل از شروع کار باید دیوار سطوح متذکره مرطوب شده با استفاده از سمنت و ریگ درشت پلاستر کاری گردد.
- در مرحله دوم قبل از اینکه پلاستر کاری (لایه یی درشت) به مقاومت نهایی برسد، باید توسط ریگ میده و سمنت صاف کاری انجام شود. در مرحله سوم باید لایه دومی و سومی همزمان پرکاری و صاف کاری گردد.
- تمام سطوح پلاستر کاری باید شاقولی باشد.
- مصالحه برای چتکه و پلاستر مطابق به لست مشخصات مخلوط گردد.

یادداشت:

پلاستر کاری های انجام شده باید برای مدت حداقل 15 روز آبدهی و مرطوب نگهداشته شود، البته که از شروع کار الی ختم کار آبدهی مربوط قرار دادی میباشد، بعد از ختم کار پلاستر کاری آبدهی و مرطوب نگهداشتن پلاستر کاری ها مربوط قرار داد دهنده خواهد بود.

Attachment: one page vendor Application form

Delivery location:

➤ Yoldoz Primary Mix School, Qaisar District, Faryab province.

Type contract: end of project work

Announcement period: 02 Feb 2023 – 14 Feb 2023

Budget: The quotation must be in Afghani Currency, including transportation and other relevant cost.

قیمت ها باید به پول افغانی و شامل تمامی مصارف از قبیل ترانسپورت و غیره باشد.
مالیه دولت طبق ماده 72 قانون مالیات افغانستان وضع و به حساب وزارت مالیه انتقال می گردد.

Quotation validation: 30 days from date of submission

The Quotation Must be Sealed and Submitted to the DAARTT Head Office before the end of bidding date and must be dropped in the bidding box.

DAARTT Office Address: Kabul City, 4th District, kulola pushta, Burje Barq Bus Stop, Street No 6, Etifaq Street, House No. 11

No: +93(0)791910566

Note:

The supplier must have a valid bank account and the Plaster work without materials.

- amount will be paid as account-to-account transfer.
- Please copy and print you are quotation in company's letterheads and give your quotation in price in fixed Afghan amount.
- Please type you are company Name, specification, the announcement number and Date on the envelope, unknown and the application received after the deadline are not considered for further process.
- The contractor is obliged to start the Plaster work without materials within 3 days after signing the contract to Yoldoz Primary Mix School
- Attaches to you are quotation is a copy of the company license, a copy of the NID card for company owners.

Vendor's Application Form

Application No.

Date:

Company Information			
Company Name:		License No:	Issue Date:
Business Type:		TIN:	Expiry Date:
Bank Account No.		Bank Name:	A/c Name:
Business Address:			
House/Aprmnt No.	Street/Block No.	District:	province:
Company E-mail:		Telephone:	Post No:
Company Owners' Information			
Director' Name:	F/Name:	National ID:	Passport No:
ID Card No.	E-mail:	Cell phones:	
Address			
House/Aprmnt No.	Street/Block No.	District:	province:
Assistant Director:	F/Name:	National ID:	Passport No:
ID Card No.	E-mail:	Cellphones:	
Address			
House/Aprmnt No.	Street/Block No.	District:	province:
Director's Signature:		A.D Signature:	