



## The Liaison Office (TLO)

Strengthening Local Resilience and Integration through Improved  
Watershed and Irrigation System

SLR-Afg

Sirth Canal Rehabilitation Project 001

DESIGN DRAWINGS  
TLO/SLR-Irrigation Project

SIRTH/KHULM SAMANGAN

SAMANGAN PROVINCE

AFGHANISTAN


April 2024

## Table of Contents

DESCRIPTION	DRAWING NO
Cover Sheet	SAMANGAN / KHULM / SIRTH / CANAL
Table of Content	SAMANGAN / KHULM / SIRTH / CANAL / 001
General Specification	SAMANGAN / KHULM / SIRTH / CANAL / 002
Legend & Abbreviation	SAMANGAN / KHULM / SIRTH / CANAL / 003
GIS Map of Sirth Canal Rehabilitation Project	SAMANGAN / KHULM / SIRTH / CANAL / 004
Contor Map of Sirth Canal Rehabilitation Project	SAMANGAN / KHULM / SIRTH / CANAL / 005
General Site Plan of Sirth Canal Rehabilitaion Project	SAMANGAN / KHULM / SIRTH / CANAL / 006
Intake plan	SAMANGAN / KHULM / SIRTH / CANAL / 007
Intake Sections	SAMANGAN / KHULM / SIRTH / CANAL / 008
Intake control gate details	SAMANGAN / KHULM / SIRTH / CANAL / 009
Spillway and controle gate details	SAMANGAN / KHULM / SIRTH / CANAL / 010
Culvert and water access structure details	SAMANGAN / KHULM / SIRTH / CANAL / 011
Main Canal plan and sections	SAMANGAN / KHULM / SIRTH / CANAL / 012
Sub canal plan and sections	SAMANGAN / KHULM / SIRTH / CANAL / 013
Joints details	SAMANGAN / KHULM / SIRTH / CANAL / 014
Regulator details	SAMANGAN / KHULM / SIRTH / CANAL / 015
Regulator details	SAMANGAN / KHULM / SIRTH / CANAL / 016
Signboard details	SAMANGAN / KHULM / SIRTH / CANAL / 017

## Notes:

- 1-All dimensions are in centimeter or as specified.
- 2- Scale as shown under each section.
- 3- Contractor must adoptde signs to site conditions under the direction and with the prior approval of the Site engineer.
- 4-All elevations are based on the local bench marks (.....Meters above datum) as shown on the site plan.
- 5-The setting out of the structure and elevations must be confirmed on the site.
- 6-All P.C.C under foundation to have cement, sand and aggregate. ratio 1:2:4.
- 7- Concrete design based on a compressive strength
- 8-Weight of RCC per unit volume  $W=2400 \text{ kgf/m}^3$
- 9-Sand or fine aggregate shall be free from salt, alkali, calcium sulphate or vegetable and it shall not contain more than 5 percent by weight of sample.
- 10-The contractor shall supply samples of cement and other construction materials when requested by the Engineer.
- 11-Water :- The water used for making and curing concrete shall be from a source approved by the Engineer and at the time of use shall be free from polluting matter.
- 12-Concrete is poured and vibrate in such a way to form a solid compact concrete.
- 13-The concrete is to be cured for 21 days and shuttering removed after instruction of engineer.
- 14- The depth of foundation and angle of wing walls is not constant it depends to the strength of soil under Foundation and site condition according to site; Site engineer can increase the depth of Foundation and can change angle and length of wing walls as per site condition.



Project Details		Directorate of Agriculture, Irrigation and Livstock of Samangan		Activities	Name	Signature
Structure Type	Canal	 داریکو دفتر • دفتر ارتباط The Liaison Office	TLO-SLR-Afg Irrigation Department	Surveyed by	Zaitullah Rasoolzai	
Province	Samangan			Checked by	Eng. Abdul Munir	
District	Khulm			Designed by	Zaitullah Rasoolzai	
Village	Sirth			Verified by	Eng.Mahmood Sadiqi	
Page No	001			Scale	As Shown	Approved by



























## GENERAL SPECIFICATIONS

- 1- The stone for stone masonry and grouted stone pitching should be good quality and approved by engineer.
- 2- All Grouted stone pitching in stilling basin and foundations should be with cement sand mortar (1:5).
- 3- All Stone Masonry Cut-off Wall should be with cement sand mortar(1:5).
- 4- Bitumen should be used in all expansion and contraction joints or as specified.
- 5- All Plain Cement Concrete should be M15(1:2:4) or as specified
- 6- All tests which are needed for RCC should be done for the new source materials or after each 20 CUM delivery.
- 7- All backfilling of canal and cut off walls should be backfill from existing excavated materials as per site engineer instruction.
- 8- The compaction tests should be done during the backfilling on the culverts should be not less than 95% of Maximum Dry Density.
- 9- All the tests should be done by an organization which is accepted by the client if any test be required from the client.
- 10- Provide expansion joint for stone masonry wall after ezch18m.
- 11- Stone for Gabion should be good quality.
- 12- Stone size for Gabion shall range between 20 cm -30 cm.
- 13- Gabion should be fabricated using galvanized Standard Wire Gauge (SWG).
- 14- Principal wires along the gabion edges(salvage wire) should be strong.
- 15- Tensile strength of gabion wire should be 38-50 kg/mm2.
- 16- Galvanized gabion wire used for mesh should have 3 mm diameter.
- 17- Galvanized gabion wire for edges should have 4mm diameter.
- 18- Mesh size for gabion basket 6cmx8cm and for mattress 8cmx11cm and should follow the Macaffere Standard
- 19- All P.C.C under footings should be of M15 (1:2:4) or as specified
- 20- The Reinforced Cement Concrete (RCC) design is based on a compressive strength of  $f_c = 250 \text{ kg/cm}^2$  or as specified
- 21- Weight per unit volume of RCC concrete  $W=2400 \text{ kgf/m}^3$
- 22- Sand or fine aggregate shall be free from salt,alkali,calcium sulphate or vegetable and it shall not contain more than 5 percent by weight of total sample.
- 23- Aggregate:- Coarse aggregate shall consist of crushed gravel with the max. size of 20mm.
- 24- The Max slump should be between 5-10 cm.
- 25- To increase the workability of the concrete, the chemical admixture (Super plasticizer) can be added.
- 26- The water used for making and curing of concrete shall be from a source approved by the Engineer and at the time of use shall be free from polluting matter.
- 27- Concrete is poured and vibrate in such a way to form a solid compact concrete.
- 28- The concrete is to be cured for 14 days or acoording to the engineer instruction.
- 29- During the cold wether concreting should be stopped or the contractor has to consider the cold weather condition concreting procedures.
- 30- All shuttering should be from plywood or steel type.
- 31- Shuttering can be removed after :
 

Side of beams,walls,columns	16-24 hours
Forms from beneath the slabs(spaning up to 6m)	14 days
Forms from beneath the slabs(spaning above 6m)	21days
- 32- Steel bar overlap should not be less than  $48 \text{ } \emptyset$  bar


Project Details		Directorate of Agriculture, Irrigation and Livstock of Samangan		Activities	Name	Signature
Structure Type	Canal	 TLO-SLR-Afg Irrigation Department		Surveyed by	Zaitullah Rasoolzai	
Province	Samangan			Checked by	Eng. Abdul Munir	
District	Khulm			Designed by	Zaitullah Rasoolzai	
Village	Sirth			Verified by	Eng.Mahmood Sadiqi	
Page No	002			Scale	As Shown	Approved by

LEGEND:-



	Center Line
	Direction of flow
	Stone Masonry
	Villages houses
	Brick Masonry
	P.C.C Block
	Gabion
	Gabion Section
	Wash/River Bed Material
	Geotextile Mattress
	Plain Cement Concrete
	Reinforced Cement Concrete
	Bank Protection
	Compacted Soil
	Hill
	H.F.L / M.W.L
	Elevation of the point is 070 m
	Elevation of the point (070m) in Plan view
	Traverse Station
	Bench Mark
	Lined Slope
	Earthen Slope
	Ground Level
	Stone Pitching/Rip Rap


ABBREVIATION:-

Av	AVERAGE	ST	STATION
BM	BENCH MARK	THK	THICKNESS
W	WIDTH	TYP	TYPICAL
C/C	CENTER TO CENTER	HFL	HIGH FLOOD LEVEL
DW	DEPTH OF WATER	U/S	UPSTREAM
DWG	DRAWING	YRS	YEARS
DIA , $\phi$	DIAMETER	Q	DESIGN DISCHARGE
D.W.L	DESIGN WATER LEVEL	W.L	WATER LEVEL
D/S	DOWNSTREAM	NTS	NOT TO SCALE
EL.	ELEVATION	R.B.L	RIVER BED LEVEL
F.B	FREE BOARD	D	DEPTH
HFL	HIGH FLOOD LEVEL		
HT.	HEIGHT		
H.G.L	HYDRAULIC GRADE LINE		
KM , km	KILOMETERE		
M ,m	METRE		
Chkd	CHECKED		
Apprd	APPROVED		
M .W .L	MAXIMUM WATER LEVEL		
MIN	MINIMUM		
No(s)	NUMBER(S)		
N.G.L	NATURAL GROUND LEVEL		
P.C.C	PLAIN CEMENT CONCRETE		
R.C.C	REINFORCED CEMENT CONCRETE		





NORTH DIRECTION

Project Details		Directorate of Agriculture, Irrigation and Livstock of Samangan		Activities	Name	Signature
Structure Type	Canal	 <p>داریکو دفتر • دفتر ارتباط The Liaison Office</p> <p>TLO-SLR-Afg Irrigation Department</p> 		Surveyed by	Zaitullah Rasoolzai	
Province	Samangan			Checked by	Eng. Abdul Munir	
District	Khulm			Designed by	Zaitullah Rasoolzai	
Village	Sirth			Verified by	Eng.Mahmood Sadiqi	
Page No	003			Scale	As Shown	Approved by









Project Details		Directorate of Agriculture, Irrigation and Livstock of Samangan		Activities	Name	Signature
Structure Type	Canal	 TLO-SLR-Afg Irrigation Department		Surveyed by	Zaitullah Rasoolzai	
Province	Samangan			Checked by	Eng. Abdul Munir	
District	Khulm			Designed by	Zaitullah Rasoolzai	
Village	Sirth	Project Name	Sirth Canal Rehabilitation	Verified by	Eng. Mahmood Sadiqi	
Page No	004	Scale	As Shown	Approved by	Samangan, PAIL Dep	



# Sirth Canal Contour Map




### Legends

- Proposed Culvert 
- Proposed Canal 
- Spillway and control gate 
- Major contour 
- Minor contour 




Project Details		 Directorate of Agriculture, Irrigation and Livestock of Samangan TLO-SLR-Afg Irrigation Department		Activities		Name	Signature
Structure Type	Canal			 وزارت زراعت، آبپاری و دامپروری وزارت مالداري و مالداري MAIL		Surveyed by	Zaitullah Rasoolzai
Province	Samangan	Checked by	Eng. Abdul Munir				
District	Khulm	Designed by	Zaitullah Rasoolzai				
Village	Sirth	Verified by	Eng. Mahmood Sadiqi				
Page No	005	Approved by	Samangan, PAIL Dep				
Project Name		Sirth Canal Rehabilitation					
Scale		As Shown					

## General Site Plan of Sirth Canal Rehabilitation Project- Samangan/Khulam




### Legends

Perposed Culvert	
Bench Mark	
Benefited Villages Homes	
Existed Villages Road	
Main Canal	
Sub Canal	
Spillway and control gate	
Grave in existing graveyard	




Project Details		Directorate of Agriculture, Irrigation and Livstock of Samangan		Activities	Name	Signature
Structure Type	Canal	 داریکو دفتر • دفتر ارتباط TLO The Liaison Office	TLO-SLR-Afg Irrigation Department	Surveyed by	Zaitullah Rasoolzai	
Province	Samangan			Checked by	Eng. Abdul Munir	
District	Khulm			Designed by	Zaitullah Rasoolzai	
Village	Sirth			Verified by	Eng.Mahmood Sadiqi	
Page No	006			Project Name	Sirth Canal Rehabilitation	Approved by
		Scale	As Shown			







BM1:  
 Latitude: 36.681362  
 Longitude: 67.6931224  
 Elevation: 456.760


BM2:  
 Latitude: 36.681190  
 Longitude: 67.6928928  
 Elevation: 457.991




Note: The dimensions of the new rehabilitate intake floor and cut-off walls are adjusted according to the needs and site condition

Project Details		Directorate of Agriculture, Irrigation and Livestock of Samangan TLO-SLR-Afg Irrigation Department			Activities	Name	Signature
Structure Type	Canal				 داریکو دفتر • دفتر ارتباط The Liaison Office	Sirth Canal Rehabilitation As Shown	Surveyed by
Province	Samangan	Checked by	Eng. Abdul Munir				
District	Khulm	Designed by	Zaitullah Rasoolzai				
Village	Sirth	Verified by	Eng. Mahmood Sadiqi				
Page No	007	Scale		Approved by			Samangan, PAIL Dep






Section A-A



Section B-B




Single mesh Ø12@20cm c/c both directions  
Intake RCC grad slab rebar details

Note: The dimensions of the new rehabilitate intake floor and cut-off walls are adjusted according to the needs and site condition.

If the excavation of cut-off walls reached the level of hard cutting, do not stop the excavation, therefore permission must be obtained from the design engineer.

Intake RCC grad Slab Rebar Schedule				
Sr/N	No	Dia of bar (mm)	Total Length of bar (cm)	Shape of bar
1	65	12mm	1056	
2	5	12mm	1720	
3	47	12mm	1320	
3	25	12mm	110	


Project Details		Directorate of Agriculture, Irrigation and Livestock of Samangan		Activities	Name	Signature
Structure Type	Canal	 دار لیاکو دفتر • دفتر ارتباط The Liaison Office	TLO-SLR-Afg Irrigation Department	Surveyed by	Zaitullah Rasoolzai	
Province	Samangan			Checked by	Eng. Abdul Munir	
District	Khulm			Designed by	Zaitullah Rasoolzai	
Village	Sirth			Verified by	Eng. Mahmood Sadiqi	
Page No	008			Scale	As Shown	Approved by



New RCC beam and slab to fixed the water control gate and iron angle to protect the control gate, 16mm dia longitudinal bar 10 no, Stirups 10mm @20cm c/c


Longitudinal bar 10 no 16mm dia, Stirups 10mm @20cm c/c

New stone masonry cut-off wall and RCC grade beam





Details of H


14 Intake Control Gate details






Note: The control gate and steel bar should be fixed in the top and grade beams according to the needs and site condition.


Project Details		Directorate of Agriculture, Irrigation and Livestock of Samangan TLO-SLR-Afg Irrigation Department			Activities	Name	Signature
Structure Type	Canal				 داریکو دفتر • دفتر ارتباط The Liaison Office	Surveyed by	Zaitullah Rasoolzai
Province	Samangan	Checked by	Eng. Abdul Munir				
District	Khulm	Designed by	Zaitullah Rasoolzai				
Village	Sirth	Verified by	Eng. Mahmood Sadiqi				
Page No	009	Scale	As Shown	Approved by		Samangan, PAIL Dep	

# 13 Spillway Control Gate details




# 15 Control Gate side details




Project Details		Directorate of Agriculture, Irrigation and Livestock of Samangan		Activities	Name	Signature
Structure Type	Canal	 داریکو دفتر • دفتر ارتباط The Liaison Office		Surveyed by	Zaitullah Rasoolzai	
Province	Samangan			Checked by	Eng. Abdul Munir	
District	Khulm			Designed by	Zaitullah Rasoolzai	
Village	Sirth	Project Name	Sirth Canal Rehabilitation	Verified by	Eng. Mahmood Sadiqi	
Page No	010	Scale	As Shown	Approved by	Samangan, PAIL Dep	






**Culvert Plan**

The length of culvert is not constant site engineer can to change the length of culvert and wing walls according to site condition




- RCC Slab 20cm thick
- Stone masonry 80cm
- PCC concrete 10cm
- Stone bolder 15 cm
- Compacted soil


**Section B-B**




**Water access structure**



**RCC Slab details**


Project Details		Directorate of Agriculture, Irrigation and Livstock of Samangan		Activities	Name	Signature
Structure Type	Canal	 داریکو دفتر • دفتر ارتباط The Liaison Office	TLO-SLR-Afg Irrigation Department	Surveyed by	Zaitullah Rasoolzai	
Province	Samangan			Checked by	Eng. Abdul Munir	
District	Khulm			Designed by	Zaitullah Rasoolzai	
Village	Sirth			Verified by	Eng.Mahmood Sadiqi	
Page No	011			Scale	As Shown	Approved by






## Plan of Sirth Main Canal


Note: Total length of the main and sub canals are measured 1900m




Typical Section A-A




Typical Section A-A with need of foundation


Project Details		Directorate of Agriculture, Irrigation and Livstock of Samangan		Activities	Name	Signature
Structure Type	Canal	 دار لیاکو دفتر • دفتر ارتباط The Liaison Office		Surveyed by	Zaitullah Rasoolzai	
Province	Samangan			Checked by	Eng. Abdul Munir	
District	Khulm			Designed by	Zaitullah Rasoolzai	
Village	Sirth			Verified by	Eng. Mahmood Sadiqi	
Page No	012			Scale	As Shown	Approved by




**Plan of Sirth Sub Canal**




**16 Canal drop and settlement details**



**Typical Section B-B**




**Typical Section B-B with need of foundation**


Project Details		Directorate of Agriculture, Irrigation and Livestock of Samangan		Activities	Name	Signature
Structure Type	Canal	 دار لیاکو دفتر • دفتر ارتباط The Liaison Office		Surveyed by	Zaitullah Rasoolzai	
Province	Samangan			Checked by	Eng. Abdul Munir	
District	Khulm			Designed by	Zaitullah Rasoolzai	
Village	Sirth	Project Name	Sirth Canal Rehabilitation	Verified by	Eng. Mahmood Sadiqi	
Page No	013	Scale	As Shown	Approved by	Samangan, PAIL Dep	




### 1 Plan view of Expansion Joint in Stone Masonry Lining





### 2 Expansion Joint Details section C-C



(10x30) mm Bitumen as Joint sealant @3m




15 mm Diameter




### 3 Details of E (contraction joints) on walls copping

### 4 Water Stopper


### 5 Section View of Expansion Joint in bed PCC

Project Details		Directorate of Agriculture, Irrigation and Livstock of Samangan		Activities	Name	Signature
Structure Type	Canal	 <p>داریکو دفتر • دفتر ارتباط The Liaison Office</p>	<p>TLO-SLR-Afg Irrigation Department</p>	Surveyed by	Zaitullah Rasoolzai	
Province	Samangan			Checked by	Eng. Abdul Munir	
District	Khulm			Designed by	Zaitullah Rasoolzai	
Village	Sirth			Verified by	Eng. Mahmood Sadiqi	
Page No	014			Scale	As Shown	Approved by






9 Main Spillway plan




11 Regulator plan




10 E-E Section of Spillway and control gates

Note: Drawing is typical for the Spillway length of wing walls, slope of spillway and direction of wing walls are adjusted according to the site needs and condition




12 F-F Section of Spillway


Note: Drawing is typical for the Spillway length of wing walls, slope of spillway and direction of wing walls are adjusted according to the site needs and condition

Project Details		Directorate of Agriculture, Irrigation and Livestock of Samangan		Activities	Name	Signature
Structure Type	Canal	 TLO-SLR-Afg Irrigation Department		Surveyed by	Zaitullah Rasoolzai	
Province	Samangan			Checked by	Eng. Abdul Munir	
District	Khulm			Designed by	Zaitullah Rasoolzai	
Village	Sirth			Verified by	Eng. Mahmood Sadiqi	
Page No	015			Scale	As Shown	Approved by






8 Cross Regulator(Water Divider) Plan




6 D-D: Cross Regulator(Water Divider)




7 G Details (Regulator Frame and Board)

- Note:
1. Majority of the cross regulators locates in the new proposed main and sub canals, in case some of the regulators located in the raw part of the canal, so the site engineer can arrange the size and length of the regulator canals flow direction and wing walls according to site condition. in addition, the regulator walls length is adjusted according to site need.
  2. All the regulators are divided by sub-regulators and the design drawing is typical for all regulators, the project site engineer can adjust its sizes according to site need.
  3. Drawing is typical for the regulator but the length function is to site condition
  4. Size of manual steel gate for water regulator should be adjusted according to site requirement


Project Details		Directorate of Agriculture, Irrigation and Livstock of Samangan		Activities	Name	Signature
Structure Type	Canal	 دار لیکو دفتر • دفتر ارتباط The Liaison Office	TLO-SLR-Afg Irrigation Department	Surveyed by	Zaitullah Rasoolzai	
Province	Samangan			Checked by	Eng. Abdul Munir	
District	Khulm			Designed by	Zaitullah Rasoolzai	
Village	Sirth	Project Name	Sirth Canal Rehabilitation	Verified by	Eng.Mahmood Sadiqi	
Page No	016	Scale	As Shown	Approved by	Samangan, PAIL Dep	



# Signboard Details




3D View





Top View

Front View



Side View



Project Details		Directorate of Agriculture, Irrigation and Livestock of Samangan		Activities	Name	Signature
Structure Type	Canal	 TLO-SLR-Afg Irrigation Department		Surveyed by	Zaitullah Rasoolzai	
Province	Samangan			Checked by	Eng. Abdul Munir	
District	Khulm			Designed by	Zaitullah Rasoolzai	
Village	Sirth	Project Name	Sirth Canal Rehabilitation	Verified by	Eng. Mahmood Sadiqi	
Page No	017	Scale	As Shown	Approved by	Samangan, PAIL Dep	

